

THE MODULAR SOLUTION FOR MANAGING USER FLOWS.

flexible, advantageous and specific design

- Made in France ()
- Prefabricated, self-contained sanitary unit
- Concrete interior and exterior structure
- Exterior finishing adapted to the environment
- Manual version
- Low maintenance cost
- Remote sanitary facility management



Modul'San 8 cabins, composite wood cladding

CONFIGURATIONS AND CLADDING



Modul'San 4-cabin model
Composite wood cladding with laundry area



Modul'San 3-cabin model Composite cladding



Modul'San 6-cabin model Polished gray concrete finish

Dimensions:

1 PRM cabin: 10.14 ft \times 7.12 ft, Height: 7.09 ft **4 non-PRM cabins:** 13.35 ft \times 7.12 ft, Height: 7.09 ft **3 cabins, including 1 PRM:** 15 ft \times 7.12 ft, Height: 7.09 ft

other dimensions on request

Main materials: Concrete, Steel.

Recommended locations: Rest areas/service stations, Industrial areas, Logistics centers, Public spaces, Camp grounds/motorhome parks

Designation: Outdoor Number of cabin(s): 1 or more

Weight: starting at 11.02 tons













facilities

& EQUIPMENT













Non PRM cabin with sink

Interior

***** FONCTIONNEMENT

- •Polished concrete walls, gray or beige
- Anti-slip, smooth finished gray concrete floor (1 floor/cabin drain)
- Smooth concrete ceiling, polyurethane paint finish
- Anti-graffiti treatment on walls
- Manual bowl flush mechanism by time-delayed pushbutton
- Switch-controlled cabin lighting
- Forced mechanical ventilation with 160 m3/h ventilation unit
- Key-locking doors

+ OPTIONS

- Stainless steel wash basin, toilet and urinal bowls
- Open or closed laundry area
- External cladding
- Shower
- Disinfection kit



Air purifier

S FINANCING

Purchase

- on a signed quote or call for bids

PROTECSAN

Protecsan has been providing maintenance and servicing, troubleshooting, cleaning services since 2000.

Today, we're able to ensure the maintenance/cleaning of your sanitary facilities via a Protecsan web interface!

nsdnu

